2. Each tender must be accompanied by a deposit of Rs. 25 in cash or in currency notes and be superscribed "Tender for the supply of furniture."

3. Information regarding design, etc., may be had at the Municipal Office, during office hours.

4. The tender must be accompanied by a statement showing the rates at which the different items specified below will be executed.

5. The final acceptance of the tender will rest with the undersigned, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days after the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful tenderer whose tender has been accepted, will be duly notified to him.

8. On acceptence of one or more tenders, the earnest money of rejected tenderers will be returned.

9. The articles should be delivered at the office on or before the end of September 1918.

List of furniture.

Serial No.	Name of furniture		Dimensions	
1	Almirahs	3	4′×6½′×1½′	All these furniture should be made of seasoned Mysore teakwood.
2	Tables with two drawers	18	2½′×4′×2½′	
3	Chairs (Bug proof)	13	Usual size.	
4	Rattan chair	1		
5	Benches	7	6′×1½′×1½′	
6	Stools	7	1½′×1½′×1½′	
7	Pigeon-holes	12	3′×1½′×1½′	
8	Teakwood boxes	12	2′×1½′×1½′	
9	Small racks for keeping registers	6	4′×1½′×1½′	
10	Record rack	2	6′×6′×2½′	
11	Pigeon-hole stand	20	3′×1½′×2′	
12	Chairs for Typists	2	As per sample.	
13	Teapoy	1	2½′×1½′×2′	
14	Folding screen	1	6′×6′	

Notice dated 11th July 1918.

The public are hereby informed that the right of removing manure in the 2nd block of the Division No. II, Bangalore City, during 1918-19, has been leased out to Mr. Nanjunda Sastri instead of to Mr. N. Siddareddi as notified in this Office Notification, dated 24th June 1918, published on page 606, Part IV of the *Mysore Gazette*, dated the 4th July 1918.

Abstract Notification dated 13th July 1918.

The attention of the public is invited to the Notification, dated the 5th July 1918, calling for tenders for the supply of road materials published in pages 619—622, Part IV of the *Mysore Gazette*, dated the 11th July 1918.

The last date for submitting tenders is 27th July 1918.

K. P. PUTTANNA CHETTY,
Honorary President.

TUMKUR DISTRICT.

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 31st July 1918, for restoring Doddamathkur Hunasekatte tank, Register No. 118, Holiyurdurga hobli, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Doddamathkur Hunsekatte tank, Register No. 118, Kunigal Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Doddamathkur Hunasekatte tank, Register No. 118, Kunigal Taluk.

No.	Items of work	Per	Quantity
	Bund at R. L. 56'00, Top width 6 feet.		
1	Earthwork to bund including watering and tamping, etc., complete	C. yd.	1,840
2	Do do for breached portion	"	3,500
3	Turfing to earth slopes both in front and rear	S. yd.	2,176
4	Burnt brick in surki mortar for core wall in breach	C. ft.	540
5	Blasting rock in breach	C. yd.	7
6	New stone revetment	"	396
7	Gravel backing	Lump sum	
8	Cutting lounge trees, etc., on the bund	"	
9	Fixing new grade stones including chiselling figures and painting, etc.	No.	8
10	New register No. stone	"	1
11	New gauge stone	"	1
12	New B. M. stones	"	2
	Sluice—Repairing the front and rear cisterns and constructing a masonry wall of 1½ foot thick for the channel near the rear cistern to a length of 25 feet.	Lump sum	
	Weir 50 feet long to the right at R. L. 50'00.		
	Levelling the high ground to R. L. 50'00 and constructing rough stone wings and apron.	Lump sum	

Notice is hereby given that sealed tenders will be received at the office of the Deputy Commissioner, Tumkur District, up to 31st July 1918, for restoring Hethenahalli Dodkere, Register No. 70, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Hethenahalli Dodkere, Register No. 70, Tumkur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Hethenahalli Dodkere Tank, Register No. 70, Tumkur Taluk.

No.	Items of work	Per	Quantity
	Bund R. L. 55'00, Top width 6 feet.		
1	Earthwork to bund including watering and tamping, etc., complete	C. yd.	4,688
2	Turfing to earthen slopes	S. yd.	4,789
3	Resetting old stone revetment with new jelly	C. yd.	50
4	New stone revetment	"	843
5	Refixing old grade stones including chiselling figures and painting	No.	15
6	Fixing new grade stones including cutting figures and painting	"	10
7	New register number stone	"	1
8	New gauge stone	"	1
9	New bench mark stones	"	2
	Sluice.—Cutting the bund, examining the tunnel and cistern, repairing them and filling it up again including watering and tamping, etc.	Lump sum	
	Weir 100 feet long to the right at R. L. 50'00.		
1	Earthwork cutting the bund and examining foundation, etc.	Lump sum	
2	Burnt brick in surki mortar	C. ft.	977
3	Burnt stone slabs, dressed	S. ft.	165
4	Surki mortar plastering	Sq.	700
5	New rough stone work	C. yd.	128

Notice is hereby given that sealed tenders will be received at the office of the Deputy Commissioner, Tumkur District, up to 31st July 1918, for restoring the Balenahalli minor tank, Register No. 123, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring the Balenahalli minor tank, Register No. 123, Sira Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Balenahalli minor tank, Register No. 123, Sira Taluk.

No.	Items of work	Per	Quantity
	Bund at R. L. 54·00. Top width 6 feet.		
1	Earthwork to bund including watering and tamping, etc., complete	C. yd.	4,172
2	New grade stones, cutting figures and painting	No.	23
3	Register No. stone do	"	1
4	Bench mark stones do	"	2
5	Gauge stone do	"	1
6	Turfing to slopes	S. yd.	3,0.9
7	Removing and resetting old stone work with ½ near jelly	C. yd.	50
8	New stone work	"	525
9	Jungle clearing	Lump sum	
	Sluice at R. L. 46·35.		
	Cutting the bund and refilling the same quantity of earth excavated including consolidation and constructing a new masonry sluice.	Lump sum	
	Weir right 200' long at R. L. 50·00.		
1	Excavating foundation for body wall, apron, clearing draft and approaches chargeable to bund.		
2	Burnt brick in surki mortar	C. ft.	1,056
3	Burnt stone slab, dressed, 6" thick	S. ft.	325
4	Surki mortar plastering	Sq.	11·00
5	New rough stone work with jelly	C. yd.	142

A. SUBRAMANYA IYER,
Deputy Commissioner.

CHITALDRUG DISTRICT.

Notice dated 6th July 1918.

A notice dated 8th March 1918, calling for the payment on or before the 31st May 1918 of the 2nd instalment of the Chitaldrug-Chikjajur Railway Debenture Loan from the subscribers was published in the *Mysore Gazette*, dated 21st March 1918, and individual notices were also issued. Most of the subscribers having failed to pay the said instalment within the prescribed time, there were representations for the extension of the time on the ground that the notices were not served on them in time.

Considering the delay that arose in the service of the notices on individual subscribers, the Chitaldrug District Board have resolved that further time till 30th September 1918, be given to the subscribers. The amount to be paid is as under:—

1. Twelve and a half per cent of the amount allotted in the case of debentures of the value of Rs. 100.
2. Rs. 5 in the case of debentures of the value of Rs. 25.

This amount may be paid into any Treasury in the Mysore State. On failure to pay the call now made within the prescribed time, the amount previously paid up will be forfeited to the District Board (*vide* condition of the prospectus published under Government Order No. 732-4—L. B. 37-15-6, dated the 2nd July 1916).

K. HANUMANTHA RAO,
For *Deputy Commissioner.*